






UZDUŽNI PROFIL, DIONICA C3



DIONICA	C3									
Nazivni promjer cijevi	280.00									
Nagib	0.10%									
Kota terena (m.n.m.)		136.11	136.06	135.98	135.96	135.92	135.91	135.91	135.89	135.90
Kota nivelete (m.n.n.)		134.21	134.20	134.19	134.18	134.17	134.16	134.16	134.15	134.15
Dubina nivelete (m)		1.90	1.86	1.79	1.78	1.76	1.75	1.75	1.74	1.75
Kota dna rova (m.n.n.)		134.09	134.10	134.09	134.08	134.07	134.06	134.06	134.05	134.05
Dubina rova (m)		2.02	1.96	1.89	1.88	1.86	1.85	1.85	1.84	1.85
Duljina dionice (m)		5.56	10.53	5.52	3.33	15.06	4.89	2.71	7.17	1.38
Stacionaža (km+m)		0+000.00	0+005.56	0+016.09	0+017.61	0+020.94	0+036.00	0+040.89	0+043.60	0+050.77

 48000 KOPRIVNICA, Mosna ulica 15, OIB: 41412434130				tel. 048/251-833 fax. 048/251-898, www.komunalac-kc.hr				
građevina		REKONSTRUKCIJA VODOVODA						
investitor		KOPRIVNIČKE VODE d.o.o.		 Marina Rodak, mag.ing.aedif.  Ovlašteni inženjer građevinarstva G 5039				
lokacija		GRAD KOPRIVNICA						
razina projekta		IZMJENE I DOPUNE GLAVNOG PROJEKTA		projektant Narcis Dergez, ing.građ.				
strukovna odrednica proj.		GRAĐEVINSKI						
oznaka projekta		02/2018 - G		zaj. oznaka proj.				
mjerilo		1000/100		mjesto KOPRIVNICA				datum 03.2018.
sadržaj		UZDUŽNI PROFIL DIONICA C3						br. lista 3.2.4.